BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
60	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Prestressed / Reinforced cement concrete grade M-20 & above	Cum	21.03	1100.0	Rupees One Thousand One Hundred Only
61	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms).	Sqm	169.80	60.0	Rupees Sixty Only
62	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as specification Rubble stone masonry in cement mortar.	Cum	33.77	270.0	Rupees Two Hundred Seventy Only
63	Easing of shutters of door.	No	2.00	100.0	Rupees One Hundred Only
64	Easing of window shutters.	No	8.00	100.0	Rupees One Hundred Only
65	Dismantling Mangalore tiles roof and stacking the material within a radius of 50 meters. A.C.Sheet roofing.	Sqm	107.59	100.0	Rupees One Hundred Only
66	Conveying the excavated debries and over burden earth etc to a lead 20 kms distances by using private vehicles this including the cost of loading and inloading charges etc	Cum	132.17	150.0	Rupees One Hundred Fifty Only
67	Earth work in excavation of foundation of structures as per drawingand technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for the work-in.Ordinary/Hard soil-Mechanical Means (Depth upto 3 m)	Cum	108.22	100.0	Rupees One Hundred Only
68	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m, after breaking of clods complete as per specifications.	Cum	82.43	200.0	Rupees Two Hundred Only
69	Filling available excavated earth (excluding rock) insides of foundations upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with a lead upto 50m. And lift upto 1.5m including cost of all labour (Inside platrform , sides and sides of the area)	Cum	95.33	150.0	Rupees One Hundred Fifty Only
70	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machinemixed, concrete laid in layers not exceeding 15 cms, thick well compacted in foundation and plinth, cost of all materials, labour HOM of machinery, curing complete as per specifications.	Cum	39.59	6000.00	Rupees Six Thousand Only

For K. DAMODAR & CO.

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jakahalli village in ward no 16.

SL No.	Description	Unit	Qty	Rates in	
				Figures	words
71	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6. edges of stones chistle dressed in courses not less than 15 cms high. bond stones at two m. apart in each course including cost of materials. labour. curing complete as per specification.	Cum	66.32	6000.0	Rupees Six Thousand Only
72	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum. with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008. machine mixed. concrete laid in layers not exceeding 15 cms thick. vibrated for all works in foundation plinth and ground floor level for roof slabs. staircase. lintles. retaining walls. return walls. walls (any thickness) including attached plasters. columns. piers. abutments. pillars. posts. struts. buttresses. string or lacing courses. parapets. coping. bed blocks. anchor blocks.& Plinths etc.. including cost of all materials. labour. HOM of machinery. curing. complete as per specifications. Columns	Cum	37.19	7300.00	Rupees Seven Thousand Three Hundred Only
73	Providing & removing centering shuttering. strutting. propping etc.. and removal of form work for foundations. footings bases of columns for mass concrete including cost of all materials. labour complete as per specifications.	Sqm	64.80	300.0	Rupees Three Hundred Only
74	Providing and removing Centering. shuttering. strutting. propping etc.. for columns. pillars. piers. abutments. post and struts. square / rectangular / polygon in plan including cost of materials. labour complete as per specification and directions of the Engineer in charge.	Sqm	82.48	500.0	Rupees Five Hundred Only
75	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregares of ready mixef concrete for RCC works laid in 15 cms thick layers and well compated including vibrating. curing.etc.. with all lead and lifts etc complete(excluisive of cost of steel and fabrication charges) Ready Mixed Cement Concrete for Beams. Staircase and Roof with M-25 Staircase	Cum	51.10	7300.00	Rupees Seven Thousand Three Hundred Only
76	Providing and removing Centering. shuttering. strutting. propping etc..and removal of from work for vertical surface such as walls at any thickness including attched plasters. butresses. plinth cills and string courses cost of all materials. labour complete as per specification	Sqm	112.54	375.0	Rupees Three Hundred Seventy Five Only
77	Providing and removing cenering. shuttering. strutting. propping etc.. and removal of form work for flat surface such as suspended floors. roofs. landings. balconies and likes. thickness upto 200 mm including cost of all materials. labour complete as per specifications.	Sqm	231.08	600.0	Rupees Six Hundred Only
78	Providing and removing centering. shuttering. strutting. propping etc.. and removal of form work for sides and soffits of beams. beam haunchings. cantilever girders. bressumers and lintles exceeding 1 m in depth incluidng cost of all materials. labour complete as per specifications.	Sqm	129.16	500.0	Rupees Five Hundred Only
79	Providing and removing centering. shuttering. strutting. propping etc.. and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials. labour complete as per specificaiton. Staircase.	Sqm	26.20	500.0	Rupees Five Hundred Only

For K. DAMODAR & CO.

Managing Partner

BRUHAT BANGALURU MAHANAGARA PALIKE

SCHEDULE - B

NAME OF THE WORK: Construction of Building and Development of Govt. School and improvements in school Premises at Jalahalli village in ward no 16.

Sl. No.	Description	Unit	Qty	Rates in	
				Figures	words
80	Providing and laying in position reinforced cement concrete of design mix M25 with OPC cement @ 340kgs. with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregtes @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	1.38	7500.0	Rupees Seven Thousand Five Hundred Only
81	Providing & removing centering shuttering,strutting, propping etc., and removal of form work for sides & soffits of beams, beam haunchings, cantilever girders, bresumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications.	Sqm	20.76	500.0	Rupees Five Hundred Only
82	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 24kgs. with 12mm and down size graded granite metal coarse aggregates @0.5175cum and fine aggregtes @ 0.345cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications.	Sqm	8.91	650.0	Rupees Six Hundred Fifty Only
83	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specificaiton.	Sqm	8.91	500.0	Rupees Five Hundred Only
84	Providing and constructing precast concrete Solid Blocks with compressive strength not less than 3.5 Newton per sqm with cement mortar 1:4 masonry (quion, jamb, closer blocks) with Solid Concrete Blocks of size (40x20x20) cms confirming to I.S 2185/1965 in Superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	215.82	1200.0	Rupees One Thousand Two Hundred Only
85	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to ceiling including rounding off corners wherever required smooth rendering.. Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification.	Sqm	221.19	300.0	Rupees Three Hundred Only
86	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing lime rendering for plastering to wall and ceiling and Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications, direction of the Engineer in charge.for Inside Plastering.	Sqm	371.24	300.0	Rupees Three Hundred Only
87	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for Outside Plastering.	Sqm	260.53	300.0	Rupees Three Hundred Only

For K. DAMODAR & CO.